



**TRENCH NOTES:**

1. SUBGRADE SOILS PREPARATION, SITE GRADING, FILL AND COMPACTION SHALL CONFORM TO MAG SECTION 301.
2. ALL DEBRIS AND EXCESS EXCAVATION MATERIAL SHALL BE REMOVED FROM THE SITE.
3. NO IMPORT MATERIAL WILL BE INCORPORATED INTO THE PROJECT WITHOUT PRIOR TESTING AND APPROVAL BY THE TOWN ENGINEER. ALL IMPORTED MATERIAL MUST BE TESTED FOR ENVIRONMENTAL CONTAMINATION.



**Town of Wickenburg**

STANDARD DETAIL

**UTILITIES TRENCH & PAVEMENT REPLACEMENT**

REVISED  
05/23/2019